

District of Columbia Water and Sewer Authority David Gadis, CEO and General Manager



Briefing on:

DC Clean Rivers Project

Briefing for:

Indiana Water Summit

September 8, 2022

DCWATER.COM



1



Overview



Separate and Combined Sewer Systems



10 to Potomac River

23 to Rock Creek

3

Magnitude of the Challenge: CSOs and Surface Flooding



Program Development



- Project required by Federal Consent Decree
- Signed by EPA, Dept of Justice, District of Columbia and DC Water
- Stipulated penalties for failure to meet specified schedules



Clean Rivers Project Performance





Project Status

- Anacostia Tunnel from Blue Plains to RFK Stadium in service since March 2018
 - Provides about 100 million gallons of storage
 - 225 mgd Wet Weather Treatment Facility at Blue Plains
- Northeast Boundary Tunnel will add 100 million gallons of storage in 2023
- System performance:

Parameter	Value
Period	Mar 20, 2018 – August 2022
Volume captured	14.23 billion gals (92% reduction)
Solids & debris captured	8,562 tons





Environmental Impact Bond (EIB) for Green Infrastructure

- Background
- Pre-construction predictions from 2016
- Construction of Rock Creek Project (RC-A)
- Post-Construction Assessment
- Findings and Lessons Learned







Why Green Infrastructure in Addition to Tunnels? Triple Bottom Line Benefits of GI



Environmenta

- Reduce runoff
- Improve air quality
- Reduce summer temperatures
- Reduce energy
- usage
- Offset climate change
 - Habitat
 improvement



Social

Enhance aesthetics

- Improve livability through green space
- Reduce scope and duration of disruption during construction



conomic

ш

- Create green jobs
- National Green Infrastructure Certification Program (NGICP)
- Enhance property values
- Improve quality of life



Background Environmental Impact Bond

- DC Water issued EIB with a principal of \$25M
 - Purchasers of the bond are Goldman Sachs Urban Investment Group (GSUIG) Real Estate Member LLC and Calvert Social Investment Foundation Inc. Facilitation by Quantified Ventures.
 - EIB is "Public Utility Subordinate Lien Multimodal Revenue Bonds Series 2016B"
- Financed first GI Project in Rock Creek (RC-A)
 - Modeled after "Pay for Success" Social Impact Bonds
 - Investors repaid based upon the effectiveness of GI in managing the volume of stormwater runoff
 - Greater volume managed would result in a larger repayment to investors
 - Lower volume managed would result in a smaller repayment to investors
- GI has never been constructed on a large scale in the District, so the EIB served as a hedge for the effectiveness of GI in managing stormwater







2016 Preconstruction Predictions Monitoring and Modeling

- Documented in
 - "Environmental Impact Bond Technical Evaluation Memorandum, dated September 13, 2016"
 - Included in Exhibit D of the Private Placement Agreement
- Flow and rainfall monitoring & modeling to predict performance of GI
- Pre-construction monitoring period:
 - March 1, 2016 June 2, 2016, used for EIB calibration
- Independent 3rd Party Technical Validator (required per Private Placement Agreement)



2016 Preconstruction Predictions Sensitivity Analysis Results

- Best- and worst-case scenarios evaluated using range of GI performance parameters
- Performed Monte Carlo analysis with 1000 simulations

Percentile	Percent Reduction	Range
Adjusted 95 th Percentile	41.3%	23%
Adjusted 5 th Percentile	18.6%	

EIB Outcome Range

Tier	Runoff Reduction	Payments
1	Greater than 41.3%	DC Water pays Outcome Payment of \$3,300,319.00 to
		Purchasers
2	18.6% to 41.3%	No Outcome Payment or Risk Share Payment
3	Less than 18.6%	Purchasers pay Risk Share Payment of \$3,300,319.00 to DC
		Water



RC-A Construction Examples of Constructed Facilities



109 facilities in metered area managing more than 19 impervious acres

Post-Construction Assessment Post-Construction Monitoring

- Sewershed, rainfall & groundwater 19 months (Mar 1, 2019 – Sep 30, 2020)
 - Sewershed and rainfall monitoring locations unchanged for Pre- and Post- monitoring periods
 - Three groundwater monitoring wells (RCAGI-18, RCAGI-42, and RCAGI-55) were relocated in the immediate vicinity as they were sited within the footprint of the GI facilities constructed
- GI practice level monitoring
 - More than 70 GI practices monitored for 6.5 months (Mar 12, 2020 – Sep 30, 2020)
 - Representative practices monitored for 17.5 months (Apr 19, 2019 – Sep 30, 2020
- Independent 3rd Party Technical Validator (required per Private Placement Agreement)





 Based on post construction monitoring, runoff reduction is estimated at 19.56%, which falls within Tier 2 outcome range established in the EIB

Tier	Runoff Reduction	Payments
1	Greater than 41.3%	DC Water pays Outcome Payment of \$3,300,319.00 to Purchasers
2	18.6% to 41.3%	No Outcome Payment or Risk Share Payment
3	Less than 18.6%	Purchasers pay Risk Share Payment of \$3,300,319.00 to DC Water

Lessons Learned: Adaptive Management to Improve Project Performance on DC Water GI and Sector-wide

 Improve valves/orifices at underdrain outlets

- Select monitoring sites to reduce stormwater flow bypassing inlets and exiting the monitored shed
- Place practices in series to promote sediment removal
- Monitor at site-level instead of at sewershed level to measure performance





All

facilities

Lessons Learned:

Adaptive Management to Improve Project Performance on DC Water GI and Sector-wide

- Maximize the space between the pavers to reduce clogging.
- Install sediment traps upstream of alley to remove sediment and distribute clean flow

Porous Pavement

- Flatten the "V" shape in the alley center to increase surface area for infiltration
- Provide maintenance access to access underdrain & orifice
- Reduce number of checkdams







Lessons Learned: Adaptive Management to Improve Project Performance on DC Water GI and Sector-wide

 Pursue open space facilities that allow for more economical construction

• Install bioretention facilities closer to intersections instead of midblock to limit parking impacts

 Construct high slope or long gutter inlets to reduce flow bypassing along the gutter

Knowledge gained was extremely beneficial:

- Incorporated into first Potomac GI Project (PR-A)
- Will be applied to subsequent GI projects
- Lessons learned will be shared with industry partners
- Can benefit District's stormwater programs 2/3 of land area in District



DC Water Green Infrastructure EIB A Success Story

- Parties pleased with end results
- Provided investors with a new sustainability investment vehicle (environmental improvements, green jobs...)
- Managed risk for DC Water: Green Infrastructure had not been constructed at this scale in the District
- Informed the Program: Incredible Value from Lessons Learned
 - Influenced improvements in design, maintenance, and monitoring approach
 - Changes in designs for future green infrastructure, field tested in Rock Creek Project A and Potomac River Project A
 - Performance Monitoring provided opportunity to optimize facilities
 - Maintenance protocols fine tuned to support performance
- Nearly \$100M of future green infrastructure to be constructed in Rock Creek watershed



Questions?

Seth Charde Senior Manager, GI DC Clean Rivers Project Phone: 202-787-4730 Email: <u>Seth.Charde@dcwater.com</u> **Special Thanks to:**



Goldman Sachs

